

ATIFIED BY THE BERRIEN COUNTY,
SURVEY PEER GROUP AS THE
FFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 348 OF 1990

[Signature]
10-23-97
for corners in

**BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

RECORDED

97 NOV -3 AM 10: 29

BERNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

_____	Located In:	Corner Code #
Berrien (County)		
1. Public Land Survey	T <u>8S</u> R <u>R19W</u>	<u>1-9</u>
_____	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

11/03/97 111#2536 A99
CORNER \$7.00
11/03/97 111#2536 A99
STATE REMIN FEE \$2.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, V.J. Strebs, in a field survey on October 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 LUCIUS LYON D.S.
SET POST 12.15 CHAINS EAST OF 17TH MILE POST ON STATE BOUNDARY
6" WHITEWOOD - N 37° E - 18 LINKS
6" BEECH - N 20½° W - 36 LINKS
 - 1886 ALBERT DREW COUNTY SURVEYOR
SET CAST IRON BAR & STONE, 12.15 CHAINS EAST OF 17TH MILE POST
10" POPLAR - 65° E 7.5 LINKS

[Signature]
REMONUMENTATION
NOV 21 1997
COMMISSION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND CAST IRON BAR WITH STONES 0.48' EAST OF RAILROAD RAIL FENCE POST

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- REMOVED CAST IRON BAR AND REPLACED WITH STANDARD CONCRETE MONUMENT WITH BRASS CAP, (STAMPED "26469/1997")
SET NAIL W/TAG IN 16" TULIP - N 10° E - 25.35'
SET NAIL W/TAG IN 8" OAK - S 30° E - 48.75'
SET NAIL W/TAG IN 18" OAK - S 30° E - 0.48'
FACE OF RAILROAD RAIL FENCE POST - EAST 0.48'

Corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *[Signature]*
Surveyor's Michigan License No. 26469

Date 31 OCTOBER 1997



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT, 1985