

RAISED BY THE _____ COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 145 OF 1990

[Signature]
5-16-00

**BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BERRIEN (County) Located In: _____ Corner Code # J-9

- | | | | | | |
|------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>8 S</u> | R | <u>19 W</u> | <u>J-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____ 5.
Private Claims _____

10/20/00 111#4516 A66
CORNER \$7.00
10/20/00 111#4516 A66
STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, V.J. Strebs, in a field survey on SEPT. 20, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEYS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER SET BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE SOUTHWEST CORNER AND THE SOUTHEAST CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" IN DIAMETER X 3 FOOT CONCRETE MONUMENT W/ B.C.R.P. BRASS CAP STAMPED 26469, 2000
WITNESS TAG IN 6" BEECH S30° W 12.73'
WITNESS TAG IN 14" BEECH S80° E 24.23'
WITNESS TAG IN 14" MAPLE NORTH 40.42'
WITNESS TAG IN 6" TULIP N 30° W 37.96'

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

RECORDED
 00 OCT 20 PM 3:33
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN



Signed by *[Signature]*
Surveyor's Michigan License No. 26469

Date 19 OCT. 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

SURVEY &
REMONUMENTATION

JAN 31 2001

LIBER 4 PAGE 216

SECTION