

RECORDED BY THE _____ COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990

[Signature]
 5-16-00

**BERRIEN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BERRIEN Located in: _____ Corner Code # K-9
 (County)

- | | | | | | |
|---------------------------------------|---|-----|---|------|-----|
| 1. Public Land Survey | T | 8 S | R | 19 W | K-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous
Property in Sec. | S | T | R | | |
| | S | T | R | | |
4. Lot No. _____, Recorded Plat _____ 5.
 Private Claims _____

10/20/00 111#4516 A66
 CORNER \$7.00
 10/20/00 111#4516 A66
 STATE REMON FEE \$2.00

Register of Deeds Stamp & File
 Number

I, V.J. Strebs, in
 a field survey on SEPT. 20
, 2000 do hereby state that under
 requirements of P.A. 74, Michigan P.A. of 1970,
 the corner points mentioned in lines 1 and 2
 above were in conformance with regulations
 and rules therefore as required in the current
 manual of survey instructions of the United
 States Department of the Interior, Bureau of
 Land Management or by a decree of a Court of
 Law and /or that the corner points mentioned
 in lines 3, 4 and 5 above were in conformance
 with the rules of the Michigan Board of Land
 Surveyors or by a Decree of a Court of Law;
 established, re-established, monumented,
 recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 LUCIUS LYON, D.S.
 SET POST 12.25 CHAINS EAST OF 18 MILE POST IN INDIANA BOUNDARY.
 24" ELM N25 °W 18 LINKS
 24" ELM N 81 °E 17 LINKS
- 1986 STEFAN - STREBS, R.L.S.; P.C.
 FOUND BROKEN OFF WELL POINT
 RESET WITH 1/2" REBAR AND I.D. CAP
 POLE BARN SPIKE IN 30" TWIN MAPLE N 40 ° W 6.44'
 POLE BARN SPIKE IN 14" MAPLE NORTH 11.89'
 POLE BARN SPIKE IN 14" MAPLE N 40 ° E 21.83'
 POLE BARN SPIKE IN 24" ASH N 80 ° E 31.53'

**SURVEY &
 REMONUMENTATION**
 JAN 31 2001
 SECTION

STATE OF MICHIGAN
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

00 OCT 20 PM 3:34

RECORDED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REBAR AND ID CAP SURROUNDED BY SMALL STONES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RESET CORNER WITH 1" X 3' IRON PIPE W/ B.C.R.P. BRASS CAP IN ROOTS OF MAPLE TREE
 WITNESS TAG IN 18" MAPLE N 5 ° E 12.25'
 WITNESS TAG IN 36" TWIN MAPLE N 50 ° E 6.12'
 WITNESS TAG IN 18" ASH WEST 30.49'
 WITNESS TAG IN 14" MAPLE NORTH 28.60'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
 Surveyor's Michigan License No. 28469

Date 19 OCT 2000