

RAVISED BY THE BERRIEN COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990

**BERRIEN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE**

5-16-00 Filing Requirement of Act 74, Mich. P.A. 1970
 For corners in

BERRIEN Located In: _____ Corner Code # L-9
 (County)

- | | | | | |
|---------------------------------------|---------|--------------|---------------|------------|
| 1. Public Land Survey | | T <u>8 S</u> | R <u>19 W</u> | <u>L-9</u> |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | | 5. |
| Private Claims _____ | | | | |

10/20/00 111#4516 A66
 CORNER \$7.00
 10/20/00 111#4516 A66
 STATE REMON FEE \$2.00

Register of Deeds Stamp & File
 Number

I, V.J. Strebs, in
 a field survey on SEPT. 20
2000, do hereby state that under
 requirements of P.A. 74, Michigan P.A. of 1970,
 the corner points mentioned in lines 1 and 2
 above were in conformance with regulations
 and rules therefore as required in the current
 manual of survey instructions of the United
 States Department of the Interior, Bureau of
 Land Management or by a decree of a Court of
 Law and /or that the corner points mentioned
 in lines 3, 4 and 5 above were in conformance
 with the rules of the Michigan Board of Land
 Surveyors or by a Decree of a Court of Law;
 established, re-established, monumented,
 recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS NOT SET IN ORIGINAL GOVERNMENT SURVEYS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER SET BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE SOUTHWEST AND SOUTHEAST CORNERS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" DIAMETER X 3 FOOT CONCRETE MONUMENT W/ B.C.R.P. BRASS CAP STAMPED 26469, 2000.
 WITNESS TAG IN 18" OAK N60°E 47.55'
 WITNESS TAG IN 20" BEECH S60°E 43.00'
 WITNESS TAG IN 14" CHERRY SOUTH 28.98'
 WITNESS TAG IN 16" MAPLE N60°W 29.37'

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS, THIS MONUMENT IS ACCEPTED
 AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.



RECORDED
 00 OCT 20 PM 3:34
 BERRIEN COUNTY, MICHIGAN
 REGISTER OF DEEDS
 BRUCE TRETNEY

Signed by _____
 Surveyor's Michigan License No. 26469

Date 19 OCT 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

**SURVEY &
 REMONUMENTATION**

JAN 31 2001

SECTION

LIBER 4

PAGE 218