

RAISED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990  
W. G. Kamer  
A-29-94  
 For corners in

09/02/94 111#2445 33  
 CORNER \$7.00  
 09/02/94 111#2445 A33  
 STATE REMON FEE \$2.00

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
 BERRIEN COUNTY MICHIGAN  
 SEP 2 4 20 PM '94  
 RECORDED

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T 8 S R 20 W	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, John G. Kamer, in a field survey on August 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 Lucius Lyon Sept. 12, 1991 V.J. Strebs W&A  
 79.00 Set Post 37 Links South of SE Cor. 13-8-21 Found 1" Rod in Mon. Box  
 13" Ash N 20° E 48 Links Found 2" Iron in Mon Box  
 7" Sugar S 43° E 25 Links North 24.58'
  - 1979 Berrien County Road Commission  
 Mon. Box Osage Orange South 20.8'  
 Teje Junction Box N 45° W 51.5 Feb. 4, 1993 John G. Kamer W&A  
 S 1/4 Cor. 18-8-20 East 2591.2' April 13, 1993 Found 1" Rod in Mon Box  
 Nov. 29, 1993 Found 2" Iron in Mon Box  
 North 24.58'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1" Rod in Mon. Box & 1993 witness ties as shown above.  
 S Edge of Rd. South 2.45'  
 P.K. in stump South 20.55'  
 Top Riser Box N 45° W 51.62'

SURVEY &  
 REMONUMENTATION  
 NOV 07 1994  
 COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-7 Set standard 3' pipe w/brass plate in existing mon. box in place of 24" x 1" rod. Corner is accepted as a careful and faithful perpetuation of the original corner.  
 Set nail w/tag in 20" stump S 01° W 20.16'  
 1" pin IP in Mon. box N 01° E 24.58'  
 Edge of Road South 2.53'  
 Centerline top of riser box N 41° W 51.01'

Signed by John G. Kamer  
 Surveyor's Michigan License No. 27449

STATE OF MICHIGAN  
 JOHN G. KAMER  
 LAND SURVEYOR  
 No. 27449  
 REGISTERED LAND SURVEYOR