

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG 16 AM 9:29

SERNICE TRETHERWAY
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

For corners in

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T 8S R 20W I-9	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

08/16/99 111#9898 A99
 CORNER \$7.00
 08/16/99 111#9898 A99
 STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on 16 June, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 LUCIUS LYON, D.S.
SOUTH BETWEEN SECTIONS 22 AND 23, 56, 41 CHAINS (IN MARSH) SET POST 4.71 CHAINS EAST OF 11 MILE POST;
9" ASH N 6° W 1.03 CHAINS;
10" LYNN N 88° W 1.26 CHAINS
- 1886 ALBERT DREW, COUNTY SURVEYOR
FOUND ORIGINAL CORNER ON STATE LINE, GOV'T BEARING (LYNN) TREE STILL STANDING N 80° W 1.26 STAKE & STONE
- 1984 WIGHTMAN & ASSOCIATES, INC. (FOUND STONE)
P.K IN 18" OAK EAST 7.05;
PK IN 20" TULIP S 80° W 21.92';
PK IN 12" OAK S 35° W 15.47;
PK IN 20" TULIP S 65° W 23.95'

DEC 28 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SECTION

16 JUNE 1999 - WIGHTMAN & ASSOCIATES, INC. FOUND STONE OVER REMAINS OF BEECH POST WITH CUT POINT IN MUCK.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED STONE & POST; RESET WITH 4" X 3" CONCRETE MONUMENT W/ B.C.R.P. BRASS CAP

- WIT TAG IN 14" HICKORY N 80° E 6.64'
- WIT TAG IN 16" TULIP WEST 21.70"
- WIT TAG IN 16" TULIP S 70° W 23.91'
- WIT TAG IN 10" LOCUST S 45° W 15.56'

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
 Surveyor's Michigan License No. 26469

Date 5 AUG 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
 JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1993
 REVISED OCT., 1995

LIBER