

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

[Signature]
5-04-99

**BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 AUG 16 AM 9:28

BERRIEN TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

08/16/99 111#9898 A99
CORNER \$7.00
08/16/99 111#9898 A99
STATE REMON FEE \$2.00

For corners in _____
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 8S	R 20W J-9
	T _____	R _____
	T _____	R _____
	T _____	R _____
2. Property Controlling in Section	S _____	T _____
	S _____	T _____
3. Miscellaneous Property in Sec.	S _____	T _____
	S _____	T _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SECTION _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on 16 June, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET IN ORIGINAL SURVEYS

- 1886 ALBERT DREW, COUNTY SURVEYOR - SET STONE IN RUN ON SOUTH SECTION LINE EQUAL DISTANCE FROM SOUTHEAST AND SOUTHWEST CORNERS. STONE EAST 50 LINKS.
- 1942 J.H. DEWEY - SW HEADWALL N 5 1/2° E 28.6'
SE HEADWALL N 66° E 37.1'
SET IRON PIPE WEST 15.4'
- 1984 WIGHTMAN & ASSOCIATES, INC. (J.G. KAMER)
FOUND WOOD STAKE THAT AGREED WITH OLD WITNESS TIES, RESET WITH 1/2" REBAR & CAP #27449
SW BRIDGE HEADWALL N 5° E 28.55'
SE BRIDGE HEADWALL N 66° E 37.16'
1" IRON PIPE WEST 16.51'
- 1990 WIGHTMAN & ASSOCIATES, INC. (J.G. KAMER)
FOUND 1/2" REBAR & CAP
SW BRIDGE HEADWALL N 5° E 28.55'
SE BRIDGE HEADWALL N 66° E 37.16'
1" IRON PIPE WEST 16.51'
- 1997 WIGHTMAN & ASSOCIATES, INC. (V.J. STREBS)
FOUND 1/2" REBAR
1" IRON PIPE WEST 16.38'
PK NAIL IN 40" QUAD OAK - S 45° E 47.55'
PK NAIL IN 14" ELM S 80° E 42.67'
PK NAIL IN 12" TULIP N 70° W 25.89'
W. EDGE OF PAVEMENT EAST 3.2' ±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

16 JUNE 1997 - WIGHTMAN & ASSOCIATES, INC. FOUND 1/2" REBAR AND REMAINS OF WOOD STAKE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3" CONCRETE MONUMENT W/B.C.R.P. BRASS CAP
IRON PIPE WEST 16.38'

WIT TAG IN 10" ELM S 70° E 43.08'
WIT TAG IN 24" TRIPLE BASSWOOD S 50° E 48.82'
WIT TAG IN 10" ELM N 80° W 25.89'
WEST EDGE OF PAVEMENT EAST 3.2 ±

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by *[Signature]*
Surveyor's Michigan License No. 26469



Date 5 Aug. 1999

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995