

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG 16 AM 9:29

BERNICE TRETHERWAY
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

For corners in

Berrien (County) Located In: Corner Code #

- 1. Public Land Survey T 8S R 20W K-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

08/16/99 111#9898 A99
 CORNER \$7.00
 08/16/99 111#9898 A99
 STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on 16 June, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 LUCIUS LYON, D.S.
 SOUTH BETWEEN SECTIONS 23 & 24 55.13 CHAINS TO SOUTH BOUNDARY
 4.96 CHAINS EAST OF 12 MILE POST.
 4" ELM N 34° E 23 LINKS.
 6" WHITEWOOD N 54° W 45 LINKS
- 1886 ALBERT L. DREW, COUNTY SURVEYOR
 STAKE WITH STONES AROUND IT
 6" WHITEWOOD N 54° W 45 LINKS
- 1990 WIGHTMAN & ASSOCIATES, INC.
 FOUND STONE AT FENCE CORNER
 PK NAIL IN 20" OAK N 40° E 9.50'
 PK NAIL IN 12" OAK SOUTH 5.25'
 PK NAIL IN 10" MAPLE S 40° E 24.30'
 PK NAIL IN 8" OAK S 30° W 20.56'
 FOUND STONE AT FENCE CORNER WEST 327.36

SURVEY R
 REF
 DEC 28 1999
 SECTION



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

16 JUNE 1999 - WIGHTMAN & ASSOCIATES, INC. FOUND STONE AT FENCE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3' CONCRETE MONUMNET W/B.C.R.P. BRASS CAP
 WIT TAG IN 16" WALNUT N 60° E 9.57'
 WIT TAG IN 12" MAPLE S 30° E 24.05'
 WIT TAG IN 10" WILLOW S 10° E 6.06'
 WIT TAG IN 8" WILLOW S 40° W 20.82'
 FOUND REBAR WEST 330.62'
 FOUND STONE WEST 326.87'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by [Signature]
 Surveyor's Michigan License No. 26469

Date 5 AUG. 1999