

**New Buffalo Township (T 8 S R 20 W)
NW Cor. Sec. 6 (A-1)**

July, 1829

Lucius Lyon, D.S.
(From East) 80.00 Set Post Cor. to Townships
7 & 8 South Ranges 20 & 21 West
Ash 9 N 56 E 31
Ash 18 N 69 W 21

**Nov., 1957
Dec., 1957**

J. H. Dewey
Found & Used Cor.
2649.15 to E ¼ Sec. 1

April 14, 1977

Robert Beland
LCRC Lb. 2 pg 233
Error in Identifying Corner - Does Not Apply

Nov. 21, 1995

John G. Kamer, Wightman and Associates
NE Cor. Sec 1-8-21
Fnd. ½" rebar 1.2' north of centerline Kruger Road
Set nail w/tag in guard post south 17.46'
Set nail w/tag in power pole N 06°W 42.25'
Set nail w/tag in 15" hickory N73°E 51.69'
Set nail w/tag in 18" maple N60°W 86.49'
Occupation N looked ok
Meas. 331+/- to centerline of Galien River
Newly resurfaced road
road may have been built up.