

**SURVEY & REMONUMENTATION**

**MAR 13 1998**

**SECTION**

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code ##
<u>GIRARD TOWNSHIP</u>		
1. Public Land Survey	T <u>5</u> S R <u>6</u> W	<u>A - 09</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
Branch County  
Recorded

10-22-1997 09:55:39

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Register of Deeds Stamp # 0156

I, EDWARD R. REED, P.S. a field survey on AUGUST 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

GIRARD TOWNSHIP

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. FIELDNOTES, R. CLARK, D.S. 1825 = "WEST BETWEEN 19 & 30. INTERSECTED W. BOUNDARY 34 LKS S OF POST. SET POST COR SECS. 19 & 30. W OAK 13 EAST 65, W OAK 12 S31E 54."  
BENNETT, 1872: "FOUND STONE."  
W. H. ROGERS, RLS, 1961 SURVEY: "IRON"  
E.R. REED, CO SURVEYOR, 1971: L.C.R.C. 1/15 = "ROGERS ADVISED ME HE MADE A THOROUGH SEARCH FOR THIS CORNER & SET 1/2" IRON. FOUND IRON SET BY ROGERS".  
BRANCH COUNTY ROAD COMM., 1984: SET MONUMENT BOX OVER IRON DURING BRIDGE REBUILDING PROJECT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ON THIS DATE I FOUND THE IRON SET BY ROGERS, NOW IN A MONUMENT BOX; TOP OF IRON IS NOW 15" DEEP. BOX NOW HAS RINGS ADDED TO TOP OF BOX, (COVER IS MISSING). SET 1/2" x 24" STEEL REBAR, SO THAT BRANCH COUNTY REMONUMENTATION CAP IS OVER OLD ROD; ADDED EXTRA RING TO BRING BOX TO ROAD SURFACE.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" x 24" STEEL REBAR, WITH BRANCH COUNTY REMONUMENTATION CAP:  
S 65 E 47.80' - NW CORNER OF TELEPHONE PEDESTAL.  
S 75 E 43.20' - SPOTTER ON TOP OF E. WOOD POST OF GUARD RAIL.  
N 60 E 85.60' - SCS TAG ON SOUTH FACE OF P. POLE.  
S 30 W 52.20' - SPOTTER ON TOP OF WOOD GUARD RAIL POST @ NW CORNER OF BRIDGE.  
NORTH 49.30' - S. FACE OF RR-TIE ANCHOR POST (FENCELINE RING NORTH).

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT MEETING HELD ON 9-18-97  
E.R. Reed, Co. Rep.  
E.R. REED, P.S.

Signed by Edward R. Reed  
EDWARD R. REED, P.S.  
Surveyor's Michigan License No. \_\_\_\_\_



7437

AUGUST 7, 1997