

**SURVEY & REMONUMENTATION**

FEB 13 2001

**SECTION**

**BRANCH COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Liber **00004** Page **0100**

STATE OF MICHIGAN  
Branch County  
Recorded

09-26-2000 10:17:12

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

For corners in

BRANCH (County)	Located In:	Corner Code #/
GIRARD TWP.		
1. Public Land Survey	T <u>5</u> S R <u>6</u> W	<u>8-03</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber **00004** Page **0100**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD R. REED, in a field survey on JUNE 29, 18 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

GIRARD TWP., T5S, R6W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	●												
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
 1825: G.L.O. FIELDNOTES OF ROBT. CLARK, JR., D.S.: "40.00 SET QR. SEC. POST".  
 1868: A. R. DAY, DEP. CO. SURVEYOR: "STONE & BRICK".  
 1874: M. KNOWLES, CO. SURVEYOR: "FD. STUMPS OF U.S. TREES & SET CORNER. SET SLEIGH SHOE & EARTHEN".  
 1890: J. H. BENNETT, SURVEYOR: "QR. CORNER-FOUND IRON PLANTED BY KNOWLES. FENCES AGREEING. NO TREES.". NOTES: SURVEY SHOWS CORNER IS 40.1 CHAINS WEST OF EAST SECTION CORNER.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I DUG FOR ANY EVIDENCE OF THE CORNER SET BY KNOWLES & FOUND BY BENNETT; HOWEVER, THIS AREA HAS BEEN PREVIOUSLY EXCAVATED TO SET A CROSS CULVET IN THE ROAD AT A DEPTH OF ABOUT 8 FT. TO 10 FT. BELOW EXISTING ROAD GRADE, AND OBVIOUSLY REMOVING THE CORNER MARKER IN THE PROCESS OF SETTING THE CULVERT.  
 FROM PRO-RATED MEASUREMENTS BASED ON BENNETT'S SURVEY OF 1890, I RESET THE CORNER FROM THE EAST LINE OF THE SECTION (CORNER TO SECTIONS 5-6-7-8).  
 SET A BRANCH COUNTY REMONUMENTATION CAP ON 1/2"x24" REBAR, SET IN CONCRETE IN A C-1 MONUMENT BOX; TOP OF BOX IS 6" BELOW ROAD SURFACE.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 BRANCH COUNTY REMONUMENTATION CAP ON REBAR IN CONCRETE, IN C-1 MONUMENT BOX:  
 N 20 W 31.10' - SPOTTER, EAST SIDE OF WOOD FENCE POST.  
 N 52 E 33.82' - REBAR WITNESS ROD IN NORTH SHOULDER OF ROADBED.  
 S 50 W 31.25' - REBAR WITNESS ROD IN SOUTH SHOULDER OF ROADBED.  
 S 58 E 49.15' - CENTER OF 6" HICKORY TREE.  
 ABOUT 2' WEST OF FENCELINE RUNNING SOUTH. (LINE OF FENCE EXTENDED NORTH)

ACCEPTED BY THE BRANCH COUNTY SURVEYOR PEER GROUP AS THE ORIGINAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON Aug 9, 2000  
*E.R. Reed*  
 E.R. REED, Co. Rep.

*Edward R. Reed*

EDWARD R. REED, P.S.

Date JUNE 29, 2000



Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 7437