

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH	Located In:	Corner Code #
(County)		
GIRARD TWP.	T <u>5</u> S R <u>6</u> W	<u>C-1</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

10-22-1997 09:55:46

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0157**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1			●										
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
NORTHWEST CORNER SECTION 5 - NORTHEAST CORNER SECTION 6-
ON COUNTY LINE

- 1825: R. CLARK jr, DEPT SURVEYOR - SET CORNER
- 1873: BENNETT, CO SURVEYOR - FOUND STAKE & BRICK
- 1885: HAMILTON, CO SURVEYOR- FOUND IRON PIN RECORDED BY BENNETT
- 1892: ID MINER, CO SURVEYOR - FOUND 3" DRAIN TILE FILLED WITH COAL
- 1965: E.R. REED, CO SURVEYOR, DUG FOR CORNER OVER CONSIDERABLE AREA, & USING OLD WITNESS, FOUND PIECES OF CLAY TILE AND RESET CORNER, SET 1" IRON BAR WITH PLATE ON TOP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON ROD WITH PLAT ON TOP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

- 14" MAPLE, N23E 28.4' TO CENTER
- 10" PINE, N48W 46.65 TO CENTER
- POWER POLE, S41W 56.16' TO FACE
- 18" WALNUT, S20W 69.1' TO CENTER
- 12" HICKORY, S10E 72.73' TO CENTER
- 2.6' NORTH OF C/L OF E-W ROAD

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON


9-10-97
E.R. Reed, P.S. Co. Rep.
E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*
EDWARD W. REED

Date JULY 18, 1997

Surveyor's Michigan License No. 33985



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28
REVISED MAY 14, 1975

REVISED JAN. 198
REVISED OCT., 199