

SURVEY & REMONUMENTATION

FEB 13 2001

SECTION

**BRANCH COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

For corners in

| BRANCH (County) | Located in: | Corner Code # |
|------------------------------------|---------------------------|---------------|
| GIRARD TWP. | T <u>5</u> S R <u>6</u> W | <u>C - 03</u> |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

09-26-2000 10:17:23

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0101**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD R. REED, P.S. in a field survey on MAY 3, ~~XX~~ 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

GIRARD TWP., T5S, R6W

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
SECTION CORNER, SEC'S. 5-6-7-8-, T5S, R6W.

- 1825: G.L.O. FIELDNOTES OF ROBT. CLARK, JR., D.S. - "80.00 SET POST COR SEC'S 5, 6, 7 & 8".
- 1890: SURVEY BY J.H. BENNETT - "SEC. CORNER. FOUND STAKES & STONE BUT NO TRACES OF U.S. TREES. CORNER WELL PRESERVED." (WITNESS NOW GONE)
- 1874: SURVEY BY M. KNOWLES, CO. SURVEYOR - (NO INFORMATION GIVEN FOR THIS CORNER).
- 1938: SURVEY BY R. V. TERRILL, REGISTERED SURVEYOR - "FOUND TWO STONES TOGETHER, BROKEN BRICK, OLD STOVE LEG AND 8" TAPERED END OF AUTO AXLE. IN CENTER OF ROAD AND IN LINE WITH FENCES NORTH & SOUTH. (HIS THREE WITNESSES ARE NOW GONE).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG AND FOUND THE TWO STONES WITH OLD AXLE SHAFT BETWEEN THE STONES.
I SET A BRANCH COUNTY REMONUMENTATION CAP ON 1/2"x24" REBAR BETWEEN THE TWO STONES & PLACED THE AXLE SHAFT BESIDE THE REBAR. PLACED A C-1 MONUMENT BOX COVER (UNABLE TO SET A BOX) OVER THE REMON. CAP.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION CAP ON REBAR, BETWEEN STONES, UNDER C-1 MONUMENT BOX COVER:
NORTH 45 EAST 56.90' - NEAR FACE OF POWER POLE.
DUE SOUTH 37.50' - FACE OF 2" DIA. STEEL ANCHOR POST, WITH FENCELINE RING. SOUTH
SOUTH 22 EAST 39.31' - CENTER OF 12" ASH TREE.
SOUTH 42 WEST 55.75' - CENTER OF 12" ASH TREE.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Aug 9, 2000

E.R. Reed.
E.R. REED, Co. Rep.

Signed by Edward R. Reed
EDWARD R. REED, P.S.



Date MAY 3, 2000

Surveyor's Michigan License No. 7437