

SURVEY & MONUMENTATION

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN

Branch County

Recorded

JAN 23 1996

09-28-1995 10:20:14

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00003 Page 0023

Register of Deeds Stamp & File Number

For corners in

BRANCH

COMMISSION

(County)

GIRARD TWP

Located In:

Corner Code ##

- | | | | |
|------------------------------------|------|------|------|
| 1. Public Land Survey | T 5S | R 6W | C-10 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Edward W. Reed, in a field survey on June 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

QUARTER CORNER COMMON TO SECTIONS 29 & 30, T5S, R6W, GIRARD TWP. BRANCH COUNTY, MI.

1825: Robert Clark, Dept. Surveyor - set corner

1970: E. J. McCombs, Consumers Power Co. - set railroad spike midway and on line between sections corners.

1973: E. R. Reed, County Surveyor - recorded corner in L.C.R. #84, found railroad spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike that was set over 1/2" iron.

Set cast iron monument box flush with road surface, 1/2"x18" iron and remonumentation cap in place of railroad spike.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-13-95

E. R. Reed, C. Rep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

N 85° E 28.8' - steel fence corner post

N 76° W 21.3' - power pole (face)

S 54° E 36.1 - face of round fence corner post

5.8' south of fenceline running east

And is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by Edward W. Reed
Surveyor's Michigan License No. 33985

Date June 14, 1995