

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BRANCH	Located In:	Corner Code #
(County)		
GIRARD TWP.		
1. Public Land Survey	T <u>5</u> S R <u>6</u> W	E-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
Branch County
Recorded

12-30-1997 10:05:32

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0193**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCTOBER 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
SECTION CORNER COMMON TO SECTIONS 8-9-16-17

- 1825: R. CLARK jr, D.S.- CORNER SET
- 1882: M. KNOWLES, D.S. - FOUND US BEARING TREE AND STAKE TO AGREE
- 1938: R.V. TERRILL, L.S. - IN SWAMPY LOCATION, GOVT.. WITS GONE, DID NOT DIG
- 1966: E.R. REED, CO. SURVEYOR - SET 1 1/4" WELL POINT AT CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FROM SURVEY OF E.R. REED AND REMAINS OF OLD FENCE LINE, LOCATED REMAINS OF 1 1/4" WELL POINT IN SWAMP AND 3' OF WATER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET (2) 3/4" X 30" REBAR IRONS ALONG SIDE OF 1/2" X 18" REBAR IRON WITH REMON CAP

- CARSONITE MARKER ALONG SIDE OF POINT
- CENTER OF 12" PINE, N75W 177.9'
- END POST OF WOOD FENCE, DUE WEST 175.5'
- CENTER OF TRIPLE MAPLE, S72W 117.6'
- CENTER OF CLUMP MAPLES, S66W 152.5'
- CENTER OF N. END BRIDGE CULVERT, S33W 188.7'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*
EDWARD W. REED

Date OCTOBER 30, 1997

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE ORIGINAL CORNER UNDER MICHIGAN PUBLIC ACT 845 OF 1980 AT A MEETING HELD ON DEC 8, 1997

E.R. Reed
E.R. REED

