

# SURVEY & REMONUMENTATION

MAR 2 1 1997

BRANCH COUNTY REMONUMENTATION CORNER  
**LAND CORNER RECORDATION CERTIFICATE** STATE OF MICHIGAN  
 Filing Requirement of Act 74, Mich. P.A. 1970 Branch County  
 Recorded

COMMISSION

For corners in  
 BRANCH (County)

Located In:	Corner Code #
T <u>5S</u> R <u>6W</u>	<u>E-12</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

10-30-1996 09:20:27

Linda Lee Morrison-Mathews  
 REGISTER OF DEEDS

Liber **00003** Page **0078**

Register of Deeds Stamp & File Number

- GIRARD TWP.  
 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5			4			3		2			
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD W. REED, in a field survey on SEPTEMBER 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 QUARTER CORNER COMMON TO SECTIONS 32, & 33, T5S, R6W, GIRARD TWP, BRANCH COUNTY, MI  
 1825: ROBERT CLARK, JR., DEP. SURVEYOR, CORNER SET  
 1865: A.R. DAY, COUNTY SURVEYOR, CORNER MARKED BY SASSAFRASS POST SET DEEP IN GROUND WITH BRICK & IRON KETTLE  
 1910: J.J. COX, SURVEYOR, FOUND OLD KETTLE IN STONE WITH STAKE IN CENTER, PLACED 3/4" GAS PIPE IN PLACE OR STAKE  
 1973: E.R. REED, COUNTY SURVEYOR, FOUND 3/4" IRON PIPE, RECORDED L.C.R.C. #065

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" IRON INSIDE OF 3/4" IRON PIPE  
 SET REMONUMENTATION CAP ON IRON  
 SET CAST IRON BOX FLUSH WITH ROAD SURFACE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON OCT. 9 1996

*E.R. Reed Co. Rep.*  
 E.R. REED

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX  
 E 30.9'-ANGLE IRON ANCHOR POST  
 W33.3' TO NE CORNER OF GARAGE WALL S  
 S70E 26.1' TO NAIL IN TELEPHONE POLE  
 N33W 59.0' TO SW CORNER COTTAGE  
 N83W 44.0' TO 12" ASH  
 N58E 56.8' TO SW CORNER OF CONCRETE RETAINING WALL  
 N20W 70.0' TO FACE OF POWER POLE  
 S20W 87.0' TO FACE OF POWER POLE



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed Date SEPTEMBER 4, 1996  
 Surveyor's Michigan License No. 33985