

**SURVEY & REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

For corners in

BRANCH (County)	Located In:	Corner Code #
GIRARD TWP.	T <u>5</u> S R <u>6</u> W	G-5
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10-22-1997 09:56:30

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber 00003 Page 0163

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JULY 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
CORNER COMMON TO SECTIONS 9-10-15-16

- 1825: R. CLARK jr, DEPT SURVEYOR - CORNER SET
- 1900: HAMILTON, CO SURVEYOR - FOUND OLD TILE WITH STAKE SET IN IT, PUT LONG STONE, OLD TIN
- 1989: E.R.REED, CO SURVEYOR - FOUND 1" SOLID IRON ROD IN CI-MONUMENT BOX IN OLD CONCRETE PAVEMENT FROM STATE HIGHWAY PLANS, RECORDED IN LCRC # II-00141
- 1994: E.W.REED, SURVEYOR, FOUND BROKEN MONUMENT BOX- REPLACED WITH NEW BOX FLUSH WITH ROAD SURFACE, REPLACED 1" IRON WITH 1/2"X18" IRON & CAP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD IN CI-MONUMENT BOX, SET REMON CAP ON IRON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON ROD IN CI-MONUMENT BOX WITH REMON. CAP

- 13.5' NORTH OF C/L ASPHALT DRIVEWAY RUNNING WEST
- 40" MAPLE, N15-30W 65.7' TO CENTER
- 36" MAPLE N8-30W 99.3' TO CENTER
- P.POLEM N45E 84.95 TO FACE
- TEL. POLE, S31W 107.97' TO FACE
- P.POLE S9E 209.30 TO FACE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

9-18-97


*E.R. Reed, P.S. Co. Rep.*  
E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed  
EDWARD W. REED

Date JULY 18, 1997

Surveyor's Michigan License No. 33985



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28  
REVISED MAY 14, 1976