

**SURVEY & REMONUMENTATION**  
**BRANCH COUNTY REMONUMENTATION PROGRAM**  
**LAND CORNER RECORDATION CERTIFICATE**

**FEB 13 2001**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
GIRARD TWP		
1. Public Land Survey	T <u>5 S</u> R <u>6 W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN  
 Branch County  
 Recorded

12-15-2000 14:05:58

Linda Lee Morrison-Mathews  
 REGISTER OF DEEDS

Liber 00004 Page 0118  
 Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

*E.R. Reed, P.S.*  
**E. R. REED, Co. REP.**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on OCT. 27, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 21 & 22, GIRARD TWP., BRANCH COUNTY, MI

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825: ROBT CLARK, JR-CORNER SET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


CORNER HAS NOT BEEN FOUND OR USED SINCE ORIGINAL GLO SURVEY  
 CORNER WAS NOT FOUND OR SET BY STATE HIGHWAY DURING CONSTRUCTION OF US-27  
 NO EVIDENCE OF CORNER FROM OCCUPATION  
 RESET CORNER ON LINE AND MIDWAY BETWEEN CORNERS NORTH AND SOUTH  
 SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE  
 SET MAG NAIL ON LINE & MIDWAY BETWEEN NE & NW  
 TOP CENTER OF CONCRETE ANCHOR POST NORTH 34.03'  
 TAG N. SIDE TELEPHONE POLE S74E 163.08'  
 CENTERLINE ROAD NORTH 1.8'  
 SW CORNER OF HOUSE N61E 159.74'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed  
 EDWARD W. REED



DATED: OCT. 27, 2000

Surveyor's Michigan License No. 33985

NOTICE  
 THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAPPING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED SEND PUBLIC TO REGISTER OF DEEDS FOR COPIES.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995