

REV. 11/1983
FEB 03 2000

SECTION

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Branch County
Filing Requirement of Act 74, Mich. P.A. 1970 Recorded

For corners in

BRANCH (County)	Located In:	Corner Code #
GIRARD TOWNSHIP		
1. Public Land Survey	T 5 S R 6 W	H - 11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

11-08-1999 15:12:36

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0018
Register of Deeds Stamp & File Number

I, Edward R. Reed, in a field survey on August 18, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

GIRARD TOWNSHIP

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
H-11: QUARTER CORNER TO SECTIONS 27 & 34, GIRARD TOWNSHIP, T5S, R6W.
G.L.O.: Robert Clark, Jr., D.S., 1825: "Set post."
Chas. Hamilton, County Surveyor, 1901: "Set long, slim stone with deposit of earthen, glass bottle & crockery. Witness: B. Walnut 5 S63W 107 (1k).
Old section corner file card: "Stone & brick."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found pointed stone, 23" below road surface, with traces of brick.
Set Branch County Remonumentation Cap on 1/2"x15" rebar, over point of stone, and set in a C-I monument box. Stabilized rebar with asphalt in monument box.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct. 6, 1999

E.R. Reed, Co. Rep.
E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
BRANCH COUNTY REMONUMENTATION CAP ON REBAR IN C-I MONUMENT BOX:
N 60 E 74.20' - CENTER OF 10" WALNUT.
N 72 E 97.11' - CENTER OF 8" WALNUT.
NORTH 28.3' - SOUTH FACE OF RR-TIE ANCHOR POST.
S 40 W 30.40' - CENTER, WEST END OF CMP DRIVEWAY CULVERT.
SOUTH 18.7' - CENTER, EAST END OF CMP DRIVEWAY CULVERT.



Signed by [Signature] Edward R. Reed, P.S. Date August 18, 1999
Surveyor's Michigan License No. 7437