

RFC 1000000

FEB 23 2000

SECTION

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN

Filing Requirement of Act 74, Mich. P.A. 1970 Branch County Recorded

For corners in

BRANCH (County)	Located In:	Corner Code #
GIRARD TOWNSHIP		
1. Public Land Survey	T 5 S R 6 W	I - 11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

11-08-1999 15:12:45

Linda Lee Morrison-Mathews REGISTER OF DEEDS

Liber 00004 Page 0019 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

GIRARD TWP., T5S, R6W

I, Edward R. Reed, in a field survey on August 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
 SECTION CORNER, SECTION 26-27-34-35, GIRARD TOWNSHIP, T5S, R6W.
 G.L.O. : ROBERT CLARK, JR. D.S., 1825: SET STAKE.
 CHAS. HAMILTON, CO. SURVEYOR, 1901: "FD. STONE".
 MAX WALTER, MSHD, 1963: "3/4"x36" IRON PIPE." (6 WITNESSES).
 E. R. REED, CO. SURVEYOR, 1964: "FD. IRON PIPE".
 OLD SECTION CORNER FILE CARD: "STONE, IRON".

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON OCT. 6, 1999.
E.R. Reed, Co. Rep.
E.R. REED

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 CORNER MARKER, IRON PIPE, HAS BEEN REMOVED BY ROAD COMMISSION RECONSTRUCTION OF INTER-SECTION CORNER BIDWELL AND MICHIGAN ROADS, AND PLACING TWO LARGE CULVERTS ACROSS THE INTERSECTION.
 USING FIELDNOTES OF THE MICHIGAN STATE HIGHWAY DEPARTMENT FOR THE SURVEY OF HIGHWAY I-69 AND I-69 HIGHWAY PLANS, I RESET THIS CORNER TO IT'S PREVIOUS LOCATION.
 SET A BRANCH COUNTY REMONUMENTATION CAP ON REBAR, IN A C-I MONUMENT BOX, IN GRAVEL ROAD.
 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER., AS HEREBY REESTABLISHED.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 BRANCH COUNTY REMONUMENTATION CAP, ON REBAR, IN C-I MONUMENT BOX:
 N 60 E 52.30' - TOP CENTER OF TELEPHONE PEDESTAL.
 S 80 E 67.10' - SIGN "DEAD END", HIGHWAY SIGN.
 S 60 E 59.1' - TOP S. END, CMP CULVERT.
 S 43 E 47.7' - TOP S. END, CMP CULVERT.
 N 10 W 23.2' - TOP N. END, CMP CULVERT.
 S 18 W 51.80' - SIGN "DEAD END", HIGHWAY SIGN.

Signed by Edward R. Reed EDWARD R. REED, P.S.



Date AUGUST 16, 1999

Surveyor's Michigan License No. 7437