

**SURVEY & REMONUMENTATION**

**FEB 13 2001**

BRANCH COUNTY REMONUMENTATION PROGRAM

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

STATE OF MICHIGAN  
Branch County  
Recorded

12-15-2000 14:06:31

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **00004** Page **0121**  
Register of Deeds Stamp & File Number

BRANCH (County)	Located In:	Corner Code #/
GIRARD TWP.		
1. Public Land Survey	T <u>5</u> S R <u>6</u> W	J - 11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

GIRARD TWP., T5S, R6W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD R. REED, P.S. in a field survey on OCTOBER 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

QUARTER CORNER TO SECTIONS 26 & 35, T5S, R6W, GIRARD TWP.;  
G.L.O.: ROBERT CLARK, JR., D.S. - 1825: "39.89 SET QR. SEC. POST BETWEEN SECS. 26 & 35, AT AVERAGE DISTANCE."  
1901: CHAS. HAMILTON, COUNTY SURVEYOR: "FOUND STONE & BRICK."  
1963: MAX WALTER, SURVEY CHIEF, MSHD: "1 1/2 IN. PIPE ON FENCELINE N & S, CENTERLINE OF BIDWELL ROAD- (FOUR WITNESSES GIVEN)"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND THE 1 1/2 INCH PIPE AS IDENTIFIED BY MAX WALTER, MSHD, SURVEY FOR HIGHWAY I-69. THERE IS NO EVIDENCE OF THE STONE OR BRICK IN THIS AREA AS REFERED TO BY HAMILTON. RECOMMENDATION OF THE PEER GROUP WAS TO ACCEPT THE PIPE USED FOR THE I-69 SURVEY BY MSHD, AS THE QUARTER-SECTION CORNER.  
I SET A 1/2"x24" REBAR, WITH A BRANCH COUNTY REMONUMENTATION CAP, IN THE PIPE, IN CONCRETE, ALL IN A C-1 MONUMENT BOX, BELOW GROUND SURFACE, AND AT EAST SIDE OF I-69 R/W FENCELINE.

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION CAP ON REBAR, IN IRON PIPE, ALL IN C-1 MONUMENT BOX:  
DUE NORTH 32.62' - CONCRETE PILLAR.  
S 30 E 20.20' - TOP, SOUTH END OF STEEL GUARD RAIL.  
N 45 E 14.05' - TOP, NORTH END OF STEEL GUARD RAIL.  
DUE EAST 6.95' - FACE OF NORTH STEEL POST FOR "DEAD END" SIGN.  
AT EAST SIDE OF N-S: RIGHT OF WAY FENCE FOR I-69 HIGHWAY.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed P.S.  
E. R. REED, C. REP.

Signed by Edward R. Reed EDWARD R. REED, P.S.

Surveyor's Michigan License No. 7437



DATE OCTOBER 9, 2000

THIS COPY IS FOR BRANCH COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983