

SURVEY & REMONUMENTATION

FEB 13 2001

BRANCH COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

STATE OF MICHIGAN
Branch County
Recorded

12-15-2000 14:06:40

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

BRANCH <small>(County)</small>	Located In: GIRARD TWP.	Corner Code ##
1. Public Land Survey	T <u>5S</u> R <u>6W</u>	K-02
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber **00004** Page **0122**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **EDWARD R. REED, P.S.** in a field survey on **NOVEMBER 3, 2000**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

GIRARD TWP., T5S, R6W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

QUARTER CORNER TO SECTIONS 1 & 2, GIRARD TWP., T5S, R6W:

1825-1826: G.L.O. FIELDNOTES OF ROBERT CLARK, JR., D.S. - "SET QTR SEC POST".

1893: SURVEY BY I.D. MINER, COUNTY SURVEYOR - "K - FOUND IRON ROD SET IN BRICK & STONE".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

USING THE LINE OF AN ANCIENT FENCELINE RUNNING WEST, C/L OF ROAD RUNNING EAST, AND SPLITTING FENCELINES RUNNING EAST, I DUG AND FOUND A PIECE OF IRON AND WHAT APPEARED TO BE A PIECE OF BRICK. DID NOT FIND A STONE, BUT DID FIND A GROUP OF STONES BY THE BRICK. ACCEPTED THIS AS THE CORNER SINCE IT FIT BOTH THE FENCELINE RING WEST & EQUAL DISTANCE BETWEEN LINE OF FENCELINES RING EAST.

SET A BRANCH COUNTY REMONUMENTATION CAP ON 1/2" x 24" REBAR STEEL ROD, IN A C-I MONUMENT BOX, IN ROAD PAVEMENT.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION CAP ON REBAR STAKE, IN C-I MONUMENT BOX:

NORTH 43 EAST 46.10' - CORNER OF L-IRON ANCHOR POST (FENCELINE NORTH & EAST).

NORTH 47 EAST 41.95' - SW CORNER OF TELEPHONE PEDESTAL.

SOUTH 44 EAST 47.00' - NW CORNER OF RR-TIE ANCHOR POST (FENCELINE EAST & SOUTH).

SOUTH 25 WEST 95.51' - CENTER OF 48" MAPLE TREE.


SOUTH 32 WEST 43.50' - TOP, WEST END OF CMP CULVERT (RUNS E-W).

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed, P.S.
E.R. REED, Co. REP.

Signed by EDWARD R. REED, P.S.

Surveyor's Michigan License No. 7437



NOTICE

Date: NOVEMBER 3, 2000

FOR BENCH
DEPARTMENTAL MAP-
USES ONLY. THIS
COPY NOT TO BE REPRODUCED
SEND PUBLIC TO REGISTER OF
DEEDS FOR COPIES.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983