

SURVEY & REMONUMENTATION

FEB 03 1999

SECTION

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
GIRARD TWP		
1. Public Land Survey	T <u>5 S</u> R <u>6 W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

11-04-1998 15:48:02

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 9-09-98

E.R. Reed Co. Rep.
E.R. REED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on AUGUST 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

CORNER COMMON TO SECTIONS 13-14-23-24

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: R. CLARK, JR., D.S. - CORNER SET
- 1902: CHAS. HAMILTON, CO. SURVEYOR - FOUND BIG CYLINDRICAL STONE
- OLD CORNER RECORDS OF E.R. REED, CO SURVEYOR - STONE, BRICK & PLOWPOINT, NO WITNESS
- 1964: E.R. REED, CO SURVEYOR - FIELD NOTES INDICATE DIPPED IRON UNDER PAVEMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 10" SQUARE IRON, DUG LARGE HOLE AND FOUND NOTHING ELSE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH REMON CAP IN PLACE OF FOUND IRON, SET CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE.

- TEL PED S 85 W 142.9' TO FACE
- 26" WALNUT S 73 W 69.5' TO CENTER
- POWER POLE S 07 W 35.6' TO FACE
- TEL PED S 68 E 104.4' TO FACE

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*

EDWARD W, REED

Surveyor's Michigan License No. 33985

Date SEPTEMBER 9, 1998

Liber 00003 Page 0227

