

REF. 100-100000

FEB 0 2000

SECTION

BRANCH COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Branch County
Filing Requirement of Act 74, Mich. P.A. 1970 Recorded

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>BRANCH COUNTY</u> | Located In: | Corner Code # |
| GIRARD TWP | | |
| 1. Public Land Survey | T <u>5 S</u> R <u>6 W</u> | <u>K-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ | _____ |
| | T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ | _____ |
| | T _____ R _____ | _____ |
| Property in Sec. | S _____ | _____ |
| | T _____ R _____ | _____ |

11-08-1999 15:12:54

Linda Lee Morrison-Matheus
REGISTER OF DEEDS

Liber 00004 Page 0020

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 8, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded On this certificate.

CORNER COMMON TO SECTION 25, 26, 35 & 36, GIRARD TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: ROB'T CLARK, JR., D.S., CORNER SET
- 1901: CHAS. HAMILTON, CO. SURVEYOR, FD STONE WELL PLANTED WITH BRICK AROUND
- 1957: H.L. RUSSELL, R.L.S., SURVEY TIED TO CORNER
- 1963: MAX WALTER, MSHD, SURVEY, 3/8" BOLT RAISED FLUSH WITH 1" SQ. BOLT, WITNESSED
- 1973: DAVID BOONE, R.L.S., SURVEY TIED TO CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" CAPPED IRON OVER STONE (UNABLE TO READ CAP), FITTING ONE REMAINING WITNESS OF STATE MSHD NOTES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" X 18" IRON WITH REMON CAP IN CAST IRON BOX
- S 25 W 66.32' CENTER OF 29" MAPLE (NOW DEAD)
- N 51 E 40.96 SW CORNER TELEPHONE PEDESTAL
- S 32 E 33.4' EAST END E-W ROAD CULVERT
- S 42 W 30.3' WEST END E-W CULVERT
- N 43 W 72.4' CENTER OF 4" TWIN ASH
- N 8 W 153.10 TAG EAST SIDE OF POWER POLE
- S 56 W 51.2' CENTER OF 8" BUTTERNUT

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

EDWARD W. REED

Date JULY 8, 1999

Surveyor's Michigan License No. 33985

ACCEPTED BY THE BRANCH COUNTY SURVEYOR PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 343 OF 1990 AT A MEETING HELD ON Oct. 6 1999
E.W. Reed Co. Rep.
E.R. REED

