

SURVEY & REMONUMENTATION

FEB 08 1999

SECTION

BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BRANCH COUNTY</u> GIRARD TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>5 S</u> R <u>6 W</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

11-04-1998 15:48:09

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
7-09-98

E.R. Reed Co. Rep.

E.R. REED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on AUGUST 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

QUARTER CORNER COMMON TO SECTIONS 1 & 12

A. Description of original monument and accessories and/or subsequent restoration:
1825: R. CLARK, JR, D.S. - CORNER SET
OLD SURVEYOR RECORDS OF E.R. REED, CO. SURVEYOR - STONE & BRICK WITH WITNESS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NOTHING, APPEARS TO BE REMOVED IN ROAD BUILDING, RESET FROM WITNESS OF OLD CORNER NOTES OF E.R. REED. CO SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON ROD WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

- 28" OAK S 57 W 60.0' TO CENTER
- 6" ROUND WOOD FENCE POST SOUTH 33'
- 18" ELM S 25 E 36.6' TO CENTER
- 6" ROUND WOOD N 10 W 33.5' TO FACE
- 20" MAPLE N 55 E 51.4' TO CENTER

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

Date SEPTEMBER 9, 1998

EDWARD W, REED

Liber 00003 Page 0228

Surveyor's Michigan License No. 33985

