

FEB 08 1999

SECTION

BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH COUNTY
GIRARD TOWNSHIP

Located In:

Corner Code #

- 1. Public Land Survey T 5 S R 6 W L-7
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

STATE OF MICHIGAN
Branch County
Recorded

11-04-1998 15:48:15

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 13 AND 24, GIRARD TWP

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: R. CLARK, JR., D.S., CORNER SET
- 1902: C. HAMILTON, CO. SURVEYOR, IRON BAR AND BRICK
- 1964: ER REED, COUNTY SURVEYOR, SURVEY TIED TO CORNER

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1998 AT A MEETING HELD ON 9-09-98

E.R. Reed Co. Rep.

E.R. REED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON ROD WITH BRICK AND GLASS AROUND
REMOVED 3/4" IRON ROD AND SET 1/2" X 18" REAR IRON WITH REMONUMENTATION CAP
SET CI MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON WITH REMONUMENTATION CAP IN CI MONUMENT BOX

- SE CORNER OF HOUSE N 10 W 91.25'
- FACE OF POWER POLE S 80 W 132.75'
- CENTER OF 12" TWIN MAPLE N 60 W 79.2'
- FACE OF 4" SQUARE CORNER POST N 48 E 44.5'
- FENCE ROW RUNNING NORTH WEST 32.7'
- CENTERLINE OF GIRARD ROAD SOUTH .70



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed

EDWARD W, REED

Surveyor's Michigan License No. 33985

Date SEPTEMBER 9, 1998

Liber 00003 Page 0229