

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

STATE OF MICHIGAN
Branch County
Recorded

12-15-2000 14:06:51

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0123

Register of Deeds Stamp & File Number

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
GIRARD TWP		
1. Public Land Survey	T <u>5 S</u> R <u>6 W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E.R. Reed, P.S.
E. R. REED, Co. Rep.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on NOV. 3, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER OF SECTIONS 24 AND 25, GIRARD TOWNSHIP, BRANCH COUNTY, MICHIGAN.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1825: R. CLARK, JR.-CORNER SET
1865: A.R. DAY-STONE AND BRICK
1901: HAMILTON-STONE WELL SET, FENCE LINES AGREEING; N & S


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FENCE LINES NOW GONE
AT POINT ON LINE AND MIDWAY BETWEEN CORNERS EAST AND WEST
UNABLE TO LOCATE ANY EVIDENCE OF CORNER
POINT FALLS ON LINE BETWEEN RAILROAD POST-600 +/- SOUTH AND WOOD PST 250 +/- NORTH
SET POINT ON LINE AND MIDWAY BETWEEN SECTION CORNER EAST AND WEST
SET 1/2" X 18" REBAR IRON WITH CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 1/2" X 18" REBAR IRON WITH CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE
CENTERLINE ROAD SOUTH 4.0'
4" BIRCH N18E 31.8'
3" MAPLE S33E 47.3'
SW CORNER OF HOUSE ADDITION N56E 126'
SW CORNER BARN N8E 169'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W. REED

Surveyor's Michigan License No. 33985



NOTICE
THIS COPY IS FOR BRANCH DATED: NOV. 3, 2000
COUNTY DEPARTMENTAL MAP-
THIS PURPOSES ONLY. THIS
COPY NOT TO BE REPRODUCED.
SEND PUBLIC TO REGISTER OF
DEEDS FOR COPIES.