

FEB 2 2000

SECTION

BRANCH COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN  
Filing Requirement of Act 74, Mich. P.A. 1970

Branch County  
Recorded

11-08-1999 15:13:12

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber 00004 Page 0022

Register of Deeds Stamp & File Number

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
GIRARD TWP		
1. Public Land Survey	T <u>5 S</u> R <u>6 W</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JULY 6, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

EAST QUARTER CORNER, SECTION 1, GIRARD TWP.

A. Description of original monument and accessories and/or subsequent restoration:

1825: JOHN MALLET, D.S., CORNER SET  
1907: CHARLES HAMILTON, SURVEY OF SEC. 6, BUTLER TWP. FOUND STONE FOR GIRARD, 45 LINKS S. OF BUTLER CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 18" POINTED STONE FITTING WITNESS OF HAMILTON (45 LINKS S. OF BUTLER COR.) 12" BELOW GRAVEL ROAD  
REMOVED STONE TO SET CI-MONUMENT BOX TO GRADE  
PLACE RR SPIKE BELOW 1/2" X 18" REBAR IN CAST IRON MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR WITH REMON CAP IN CAST IRON MONUMENT BOX

N 60 W 14.0 CENTER OF 22" ASH  
N 26 W 30.0 CENTER OF 10" TWIN OAK  
S 03 E 159.70 NW CORNER E CENTER BRIDGE HEADWALL  
NORTH 29.38 BUTLER CORNER  
8' WEST OF N-S GRAVEL ROAD

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed  
EDWARD W. REED

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct. 6, 1999  
E. W. Reed  
E. W. REED



Date JULY 6, 1999