

FEB 23 2000

BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Filing Requirement of Act 74, Mich. P.A. 1970 Branch County Recorded

SECTION

For corners in

BRANCH _____ (County)	Located In:	Corner Code #
GIRARD TWP.		
1. Public Land Survey	T <u>5</u> S. R <u>6</u> W	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

12-30-1999 11:01:08

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0052**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCT. 21, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SOUTHEAST CORNER TO SECTION 12
NORTHEAST CORNER TO SECTION 13

1825: JOHN MULLETT, CORNER SET
1825: ROBERT CLARK, JR.-GLO OFFSET OF 31 LINKS
SURVEYOR'S OLD NOTES INDICATE TILE & STONE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

DEC. 07, 1999

E.R. Reed, P.S.
E.R. REED


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG @ GLO OFFSET & FOUND 10" POINTED STONE (NO TILE)
SET 1/2" x 18" REBAR IRON WITH REMON CAP IN CAST IRON MONUMENT BOX 4" BELOW GRAVEL ROAD SHOULDER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" x 18" REBAR IRON WITH REMON CAP IN CAST IRON BOX	
POST N77W	137.30'
TELEPHONE POLE N83W	213.66'
TELEPHONE POLE N71W	186.3'
10" OAK S36W	22.9'
BUTLER CORNER A-5	NORTH 21.06'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Edward W. Reed
EDWARD W. REED
Surveyor's Michigan License No. 33985

Date OCT 21, 1999