

SURVEY & REMONUMENTATION

FEB 13 2001

BRANCH COUNTY REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74; Mich. P.A. 1970

SECTION

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
GIRARD TWP		
1. Public Land Survey	T <u>5 S</u> R <u>6 W</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
Branch County
Recorded

12-15-2000 14:07:00

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0124**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E. R. Reed, P.S.
E. R. REED, Co. Rep.

I, EDWARD W. REED, in a field survey on NOV. 2, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHEAST CORNER OF SECTIONS 24, GIRARD TOWNSHIP, BRANCH COUNTY, MICHIGAN.

A. Description of original monument and accessories and/or subsequent restoration:

1825: MULLET-CORNER SET
OLD NOTES OF COUNTY SURVEYOR INDICATE 18" GREEN STONE AND BRICK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

AT GLO OFFSET FROM BUTLER CORNER AND IN LINE WITH EXISTING FENCE LINE RUNNING NORTH, DUG FOR CORNER, NOTHING FOUND
SET CORNER IN LINE WITH FENCE LINE RUNNING NORTH AND AT GLO OFFSET FROM BUTLER CORNER
SET 1/2" X 18" REBAR IRON WITH CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 1/2" X 18" REBAR IRON WITH CAP IN CAST IRON-REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE

BUTLER CORNER	SOUTH	36 LINKS
6" ANCHOR POST	NORTH	8.0'
TELEPHONE PEDESTAL	N45W	34.6'
60" MAPLE	N50W	51.5'
CENTER OF STANDING PIPE	S35W	45.4'
EAST END OF ROAD CULVERT	S5E	61.4'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

DATED: NOV. 3, 2000

Surveyor's Michigan License No. 33985

NOTICE
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAP-DRAWING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED AND PUBLIC TO REGISTER OF DEEDS FOR COPIES.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

