

**SURVEY &  
REMONUMENTATION**

MAR 13 1998

**SECTION**

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>BRANCH</u><br>(County)             | Located In:               | Corner Code # |
| UNION TWP.                            | T <u>5</u> S R <u>7</u> W | <u>A-5</u>    |
| 1. Public Land Survey                 | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |

10-22-1997 09:58:40

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **00003** Page **0181**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on April 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
|    | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:  
SOUTHWEST CORNER SECTION 7, NORTHWEST CORNER SECTION 18

1826: R. CLARK, jr, - CORNER SET  
OLD SURVEY NOTES INDICATE STONE AND/OR IRON  
1973: E.R. REED - DUG FOR CORNER, FOUND OLD GATE LATCH (IRON) EXACTLY ON FENCELINE RUNNING EAST, ALSO FOUND PIECE OF TILE, FITS FENCELINE OF OLD SCHOOL SITE, SET RLS CAPPED IRON IN PLACE OF OLD GATE LATCH, RECORDED IN LCRC # 0073

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND ERR CAPPED IRON STAKE


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET REMON CAP ON 1/2" EXISTING IRON, SET CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

CENTER OF 48" MAPLE, EAST 19.0'  
CENTERLINE OF NORTH-SOUTH ROAD, WEST 10.4'  
IN LINE WITH FENCELINE RUNNING EAST  
NAIL/SHINER SOUTH SIDE POWER POLE, N17W 105.12'  
NAIL/SHINER EAST SIDE POWER POLE, S25W 110.41'  
122 LINKS SOUTH OF M-5 SHERWOOD

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed Date April 20, 1997  
EDWARD W. REED

Surveyor's Michigan License No. 33985



ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 945 OF 1990 AT A MEETING HELD ON

E.R. Reed P.S.Co.Rep.

**E.R. REED**

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28  
REVISED MAY 14, 1975

REVISED JAN., 198  
REVISED OCT., 199