

FEB 06 1999

SECTION

BRANCH COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH	Located In:	Corner Code #
(County) UNION TOWNSHIP		
1. Public Land Survey	T <u>5S</u> R <u>7W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
Branch County  
Recorded

12-07-1998 13:53:46

Linda Lee Morrison-Mathews  
REGISTERED LIBER 000035 Page 0250

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on AUGUST 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 29, 30, 31 AND 32

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY ROBERT CLARK, JR, D.S. 1826 SURVEY BY E.L. MINER COUNTY SURVEYOR 1938, REESTABLISHED CORNER BY PROJECTING LINE FROM SE CORNER OF SECTION 29 WEST OVER S 1/4 POST SAME DISTANCE FROM S 1/4 POST AS MEASURED FROM SE CORNER TO S 1/4 POST, SET 4"X4"X4' CONCRETE POST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT BY MINER, TOP BROKEN OFF BUT REMAINDER STRAIGHT, ABOUT 1.0 FOOT BELOW ROAD SURFACE. SET 1/2" IRON WITH REMONUMENTATION CAP IN IRON PIPE IN CENTER OF EXISTING CONCRETE MONUMENT AND PLACED MONUMENT BOX OVER FLUSH WITH BITUMINOUS SURFACE.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

11-04-98

E.R. Reed Co. Rep.  
E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON WITH BRANCH COUNTY REMONUMENTATION CAP IN MONUMENT BOX.  
UTILITY POLE, S67°W 106.16 FEET SET SPOTTER IN SOUTHERLY SIDE  
20" WALNUT, S11°W 235.20 FEET SET SPOTTER IN WESTERLY SIDE  
12" WALNUT, N07°E 115.70 FEET SET SPOTTER IN EASTERLY SIDE  
28" WALNUT, N21°W 108.86 FEET, SET SPOTTER IN EASTERLY SIDE  
14 FEET, MORE OR LESS, EAST OF CENTERLINE OF NORTH AND SOUTH ROAD  
6 FEET, MORE OR LESS, NORTH OF CENTERLINE OF EAST AND WEST ROAD

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]  
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date OCT 1, 1998

