

**SURVEY & REMONUMENTATION**

MAR 13 1998

**SECTION**

**BRANCH COUNTY REMONUMATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u> UNION TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>5</u> S R <u>7</u> W	<u>E-11</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
Branch County  
Recorded

12-30-1997 10:06:09

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **00003** Page **0198**

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on DECEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**CORNER COMMON TO SECTIONS 28-29-32-33**

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: R. CLARK, JR., DEPT SURVEYOR - CORNER SET
- 1878: BENNETT, SURVEYOR - STONE
- 1975 :R. CARR, SURVEYOR - SET 1/2" IRON STAKE 35 FEET FROM IRON ANCHOR POST S.W., AND IN LINE WITH FENCE NORTH, RECORDED IN LCRC # 00146
- 1991: D. ANDREWS, SURVEYOR - FOUND IRON AGREEING WITH LCRC # 00146, RE-RECORDED IN LCRC # II-0171

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON ROD AGREEING WITH LCRC # II-0171  
SET CI-MONUMENT BOX OVER AND FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON ROD WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

- NAIL & CAP IN 12" ELM, S 15 E 88.20'
- NAIL & CAP IN P.POLE, S 25 W 78.26'
- NAIL & CAP IN 10" ELM, NORTH 43.15'
- EAST END OF ROAD CULVERT, S 45 E 30.3'
- WEST END OF ROAD CULVERT, S 45 W 31.0'
- C/L OF E-W ROAD, NORTH 5.3'
- IRON ANCHOR POST, S.W. 35'
- IN LINE WITH FENCE NORTH

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-08-97

E.R. Reed  
**E.R. REED**



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed  
EDWARD W. REED

Date DECEMBER 3, 1997

Surveyor's Michigan License No. 33985