

FEB 08 1999

BRANCH COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

000003 Page 0252

SECTION

For corners in

<u>BRANCH COUNTY</u> UNION TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>5</u> S <u>R</u> 7 W	<u>G-05</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

STATE OF MICHIGAN  
Branch County  
Recorded

12-07-1998 13:54:00

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY  
SURVEY DEPT GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT 935  
OF 1996 AT A MEETING HELD ON

11-04-98

*E.R. Reed, Co. Rep.*

E.R. REED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on OCTOBER 30, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 9-10-15-16

A. Description of original monument and accessories and/or subsequent restoration:

1825: R. CLARK, JR., DEPT SURVEYOR - CORNER SET  
1856: A.R. DAY, CO SURVEYOR - STONE OVER STAKE  
1991: F.J. CUTCHER, SURVEYOR - IRON OVER STONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND F.J. CUTCHER'S CAPPED IRON OVER STONE 20" DEEP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON OVER CUTCHER'S IRON IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE  
SET REMON. CAP ON REBAR.  
2" ROUND STEEL ANCHOR POST NORTH 27.67'  
WITNESS TAG IN W. SIDE 10" OAK S 47 E 90.74'  
BASE OF SQUARE CONC. POST N 38 W 39.7'  
IN LINE WITH FENCE LINE RUNNING NORTH

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*  
EDWARD W, REED

Surveyor's Michigan License No. 33985

Date NOVEMBER 4, 1998



	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												