

SURVEY &  
REMONUMENTATION

APR 26 1995

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-16-94

E. P. Reed, C. Rep.

COMMISSION  
BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Branch (County)	Located In:	Corner Code =#
UNION TOWNSHIP 1. Public Land Survey	T <u>5</u> SR <u>7</u> W	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
Branch County  
Recorded

12-28-1994 15:01:02

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Libe	A	B	C	D	E	F	G	H	I	J	K	L	M
000002													
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. Edward W. Reed, in a field survey on December 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 14, 15, 22, and 23, Town 5 South, Range 7 West, Union Township, Branch County, Michigan.

- 1825: : Brookfield, corner set
- 189 : Hamilton, found corner, with both US witness trees
- 1982: McMachen, found iron pipe 15" below road surface, set 1/2" capped iron
- 1985: Carr, found iron stake
- 1990: E. W. Reed, found iron stake over pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron capped #16935. Nothing found below iron.  
Reset 1/2" x 18" rebar, remonumentation cap and cast iron box flush with road surface

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-16-94  
E. Reed, C. Rep.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" rebar as noted above:
- N 60 E 61.08' utility pole
- S 20 W 78.0' NE corner of house
- N 72 W 105' telephone pole
- S 60 W 88.7' 54" maple

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed  
EDWARD W. REED  
Surveyor's Michigan License No. 33985

Date December 14, 1994