

**SURVEY & REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #	
<u>UNION TOWNSHIP</u>			
1. Public Land Survey	T <u>5</u> S <u>R</u> 7 W	<u>I - 8</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN  
Branch County  
Recorded

10-22-1997 09:59:02

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber 00003 Page 0184

Register of Deeds Stamp & File Number  
Liber 00003 Page 0184

UNION TOWNSHIP

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EDWARD R. REED, in a field survey on JULY 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. FIELDNOTES: R. Clark, Dep. Surveyor, 1826: "Set qtr sec post," (3 witnesses-now gone).
- BENNETT, 1874: "Fd US tree, planted plough point & brick."
- M. KNOWLES, Dep. Co. Surveyor: "Fd stone".
- E.R. REED, Co. Surveyor, 1970: "Found brick but no stone. Set 3/4"x18 steel pin" Established Witnesses to corner.
- R. CARR, RLS, 1985: "Fd. 1/2" iron." (Witnesses as given by Reed in 1970).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

From prior witnesses I used in 1970, I dug and found the 3/4" x 18 steel pin previously set.

This date I replaced the steel pin with a 1/2"x 24" steel rebar rod set in concrete with Branch County Remonumentation Cap on top and placed same in a C-I monument box. Top of box is 8 inches below road surface.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" x 24" STEEL REBAR SET IN CONCRETE WITH BRANCH COUNTY REMONUMENTATION CAP, IN C-I MONUMENT BOX:
- North 28.9' - Steel corner Post.
- N25E 36.5' - Center of 36" Walnut stump.
- S50E 32.2' - Center of 18" Wanut.
- S45E 32.3' - NW corner square concrete anchor post.
- S45W 33.4' - NE corner square concrete anchor post.
- In line with fenceline running North & center of roads E-W-S.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97  
 E.R. Reed, Col. P.S.  
 E.R. Reed, P.S.



Signed by Edward R. Reed  
 Edward R. Reed, P.S.  
 Surveyor's Michigan License No. 7437

Date July 7, 1997