

**SURVEY & REMONUMENTATION**

**MAR 13 1998**

**SECTION**

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 STATE OF MICHIGAN

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #	
UNION TOWNSHIP			
1. Public Land Survey	T <u>5</u> S R <u>7</u> W	<u>1 - 9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Branch County  
Recorded  
10-22-1997 09:58:54

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS  
Liber **00003** Page **0183**

Register of Deeds Stamp & File Number

UNION TOWNSHIP

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD R. REED, in a field survey on JULY 10, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. FIELDNOTES: R. CLARK, D.S. 1826 = "80.00 ESTABLISHED COR SEC. 22, 23, 26 & 27. SUGAR 12 IN FOR POST".  
 BENNETT, 1874: "SEC. COR. FOUND IRON AND DEPOSIT. MARKED TREES TO DENOTE CORNER".  
 E.R. REED, CO SURVEYOR, 1971: L.C.R.C. 1/04 = "FOUND STONE, SURROUNDED BY BRICK AND AN IRON BAR, 12 INCHES BELOW ROAD SURFACE".  
 SURVEYS BY E. R. REED IN 1974, 1980 & 1985 REFERENCED TO THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND THE IRON BAR OVER STONE, SURROUNDED BY BROKEN BRICKS, AS NOTED ON L.C.R.C. 1/04. REMOVED IRON BAR AND REPLACED WITH 1/2" STEEL REBAR WITH BRANCH COUNTY REMONUMENTATION CAP, SET IN CONCRETE, OVER STONE; ALL PLACED IN C-I MONUMENT BOX, (TOP OF BOX IS 4 INCHES BELOW ROAD SURFACE.)


AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" STEEL REBAR WITH BRANCH COUNTY REMONUMENTATION CAP, SET IN CONCRETE, OVER STONE; ALL PLACED IN C-I MONUMENT BOX, (TOP OF BOX IS 4 INCHES BELOW ROAD SURFACE.):  
 N 30 E 43.0' - S.W. CORNER OF SQ. CONCRETE ANCHOR POST.  
 WEST 31.0' - NEAR FACE OF SQ. CONCRETE ANCHOR POST.  
 1.0 FT. NORTH OF LINE OF FENCELINE RUNNING WEST FROM ANCHOR POST.  
 S 35 W 117.8' - CENTER OF 40" TWIN-TRUNK MAPLE.  
 S 18 W 120.6' - CENTER OF 14" APPLE TREE.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97  
E.R. Reed Co. Rep.  
E. R. REED

Signed by Edward R. Reed  
 Surveyor's Michigan License No. 7437



Date JULY 10, 1997