

RE...

FEB 13 2000

SECTION

BRANCH COUNTY REMONUMATION PROGRAM STATE OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE Branch County
Filing Requirement of Act 74, Mich. P.A. 1970 Recorded

11-08-1999 15:13:38

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0025

Register of Deeds Stamp & File Number

For corners in

<u>BRANCH COUNTY</u> UNION TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>5</u> S R <u>7</u> W	<u>J-03</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___	_____
	T ___ R ___	_____
3. Miscellaneous	S ___	_____
	T ___ R ___	_____
Property in Sec.	S ___	_____
	T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on SEPTEMBER 29, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 2 & 11

A. Description of original monument and accessories and/or subsequent restoration:

1828: R. CLARK, JR. - CORNER SET
1910: W.W. COX - FOUND IRON SHAFT WELL PLANTED IN STONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 18" SOLID IRON WITH FLAGGING, ALSO SMALL STONES AROUND IRON, NO EVIDENCE OF STONE OR IRON SHAFT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX, 4" BELOW GRAVEL ROAD SURFACE.

C/L OF EAST-WEST ROAD, NORTH 8.5'
TAG IN N. SIDE P. POLE S 79 E 372.58'
TAG IN W. SIDE P. POLE S 10 W 64.58'
CENTER OF CLUMP MAPLE S 84 W 102.4'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

Date SEPTEMBER 29, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3			2		1	
3										●			
4	7		8		9		10			11		12	
5													
6	18		17		16		15			14		13	
7													
8	19		20		21		22			23		24	
9													
10	30		29		28		27			26		25	
11													
12	31		32		33		34			35		36	
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-06-1999
E. R. Reed, Co. Rep.
E. R. REED

