

SURVEY & REMONUMENTATION

APR 26 1995

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
12-16-94

E. Reed C. Rep.

BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Branch <small>(County)</small> | Located In: | Corner Code <small>##</small> |
|---------------------------------------|---------------------------|-------------------------------|
| 1. Public Land Survey | T <u>5</u> S R <u>7</u> W | <u>K 2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
Branch County
Recorded

12-28-1994 15:01:36

Linda Lee Morrison-Mathews
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Liber 00002 Page 0296

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Edward W. Reed in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 1 and 2, Town 5 South, Range 7 West, Union Twp. Branch County, Michigan.

1885: GLO notes set quarter corner
1873: Ricker, stone and cobbles set


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Proportioned actual and GLO distances north and south
Dug for corners and found nothing

Set ½"x18" rebar iron in monument box with remonumentation cap on line of north and south Section corners and midway in distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

½" Iron as noted above:
NE corner house, (not porch), S30W 232.30'
Nail & washer 2' up N. side power pole, S72W 56.50'
Nail & washer 2' up Power Pole, N27W 276.16'
in C/L N-S road



And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Edward W. Reed Date December 8, 1994

Surveyor's Michigan License No. 33985
EDWARD W. REED