

REMONUMENTATION

APR 26 1995

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-16-94.

E. Reed, Co. Rep.

BRANCH COUNTY COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Branch (County), Located In: (Town, Range, Section), Corner Code. Includes entries for Public Land Survey and Property Controlling in Section.

STATE OF MICHIGAN Branch County Recorded

12-28-1994 15:02:06

Register of Deeds Stamp & File Number LIBB-100003-10299 REGISTER OF DEEDS

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column K and row 6.

I, Edward W. Reed, in a field survey on September 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 13 and 14, Town 5 South, Range 7 West, Union Township, Branch County, Michigan
1825: GLO notes, corner set
1990: E. W. Reed, dug, unable to find corner, set 1/2" iron on line and midway between Northeast and Southeast corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" iron as set by E. W. Reed
Dug 3 1/2' below and still in road fill
Placed remonumentation cap over iron
Set cast iron monument box flush with road surface



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron as noted above:
South 40 West 87.6-Northeast corner of barn
South 88 East 85.5-20" walnut
South 33 East 48.7-32" maple
South 9.0'-centerline road West
North 36 West 48.60-near face of telephone pedestal
North 49 East 62.5'-center of 48" pine

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 23, 1994
Surveyor's Michigan License No. 33985