

SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
12-16-94

APR 26 1995

BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

E. R. Reed Co. Rep.

For corners in

<u>Branch</u>	<u>Located In:</u>	<u>Corner Code #:</u>	
(County)			
UNION TOWNSHIP			
1. Public Land Survey	T <u>5</u> S R <u>7</u> W	M-1	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling	S _____ T _____ R _____	_____	_____
in Section	S _____ T _____ R _____	_____	_____
3. Miscellaneous	S _____ T _____ R _____	_____	_____
Property in Sec.	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN
Branch County
Recorded

12-28-1994 15:02:54

Linda Deaton-Matthews
REGISTER OF DEEDS Page 0304

Register of Deeds Stamp & File Number

I, Edward W. Reed, in a field survey on December 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner common to four Townships, Burlington, and Tekonsha of Calhoun County, and Union and Girard of Branch County.
1825: Brookfield, Corner set
1873: Ricker, found well planted

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found pointed stone 16" deep with brick
Set 1/2" x 16" iron, remonumentation cap and cast iron box flush with road surface

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
N 65 E 72.5' power pole
South 52.67' power pole
S 45 W 35.47' nail and washer up 2' N side of 20" oak
S 60 E 135.9' power pole

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date December 14, 1994
Surveyor's Michigan License No. 33985
EDWARD W. REED

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

