

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

000003

Page 0107

For corners in

BRANCH (County)	Located In:	Corner Code #
SHERWOOD TWP. 1. Public Land Survey	T 5 S R 8 W	G-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
Branch County
Recorded

12-30-1996 14:11:34

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EDWARD W. REED, in a field survey on OCTOBER 15, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: J. MULLETT, DEP. SURVEYOR, CORNER SET
OLD NOTES INDICATE: SQUARE POINTED STONE & RAILROAD SPIKE

CORNER COMMON TO SECTIONS 21, 22, 27 & 28, T5S, R8W, SHERWOOD TWP., BRANCH COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" x 18" SOLID IRON WITH FLAGGING
FOUND POINTED STONE 18" BELOW IRON & RAILROAD SPIKE PLACED ON TOP OF STONE
PLACED REMONUMENTATION CAP ON IRON AND SET CAST IRON BOX FLUSH WITH ROAD SURFACE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON NOV. 13, 1996.

E. R. Reed, C.S.P.
E.R. REED



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/8" x 18" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX
S70E 57.02' TO CENTER OF 8" WALNUT
S5W 24.99' TO CENTER OF 23" WALNUT (NOW STUMP HOLE)
S60W 46.3' TO FACE OF POWER POLE
N20E 100.0' TO FACE OF TELEPHONE PEDESTAL
S82W 149.7' TO FACE OF TELEPHONE PEDESTAL
DUE E 110.1' TO WEST WALL OF GARAGE AT HOUSE NO. 997
S68W 56.5' TO GAS VALVE

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed Date OCTOBER 15, 1996
Surveyor's Michigan License No. 33987