

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

SECTION

For corners in

BRANCH _____	Located In:	Corner Code #
(County)		
SHERWOOD TOWNSHIP	T <u>5S</u> R <u>8W</u>	<u>I-13</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

12-15-2000 14:07:35

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0127

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on NOVEMBER 15, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: JOHN MULLETT, D.S. 1825
OLD SECTION CORNER FILE CARD FROM OFFICE OF E.R. REED, COUNTY SURVEYOR:
"STONE 5 LINKS W OF CORNER OF SECTION 2, MATTESON TWP"
SURVEY BY I.D. MINER 1895: SET STONE 5 LINKS WEST OF CORNER TO SECTIONS 2 AND 3, MATTESON TOWNSHIP.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1900 AT A MEETING HELD ON 11-28-2000

E.R. Reed, P.S.
E.R. REED, Co. REP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


LOCATED GENERAL LOCATION OF CORNER BY MEASURING OCCUPATION ALONG SOUTH LINE OF SECTION 34. DUG AND FOUND DEPOSIT OF BRICK IN SUB SOIL UNDER GRAVEL ROAD: DUG EAST AND FOUND A DEPOSIT OF BRICK AND EARTHEN FOR MATTESON CORNER AT 3.3 ± FEET PER MINER 1895. ACCEPTED LOCATION OF BRICK FOUND FIRST AS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BRANCH COUNTY REMONUMENTATION 1/2" STEEL ROD WITH CAP STAMPED NO. 20704 IN MONUMENT BOX 6" BELOW GRAVEL SURFACE. TELEPHONE RISER N70°E 80.85 FEET
4" ELM, N50°E 55.0 FEET (NAIL AND SPOTTER)
6" MAPLE, N05°W 26.65 FEET (NAIL AND SPOTTER)
4" ELM, N53°W 39.87 FEET (NAIL AND SPOTTER)
5" W. CHERRY, S20°W 31.15 FEET (NAIL AND SPOTTER)
CORNER TO SECTION 2 & 3, MATTESON TOWNSHIP EAST 3.3 FEET

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date Nov 28, 2000
Surveyor's Michigan License No. 20704



NOTICE
THIS COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAILING PURPOSES ONLY. THIS COPY NOT TO BE REPRODUCED OR SENT PUBLIC TO REGISTERED DEEDS FOR COPIES.