

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BRANCH (County)	Located In:	Corner Code #
SHERWOOD TWP.	T <u>5</u> S R <u>8</u> W	<u>J-9</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
Branch County
Recorded

10-22-1997 09:58:25

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0179**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on SEPTEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9									●				
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1826: J. MULLETT, DEPT. SURVEYOR - CORNER SET
1969: E.R. REED, CO. SURVEYOR - FOUND STONE, WITNESSED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
STONE NOW GONE, RESET POINT FROM WITNESS OF E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD GRADE
12" WALNUT, N3W 35.0'
48" MAPLE S1E 21.5'
48" DOUBLE MAPLE, (NOW STUMP) S65W 59.7'
1' WEST OF FENCE SOUTH
LINE OF WEST WALL OF HOUSE, WEST 150.8'
NAIL & WASHER S. SIDE POWER POLE, N29W 72.09'


ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
Sept. 10, 1997
E. Reed, Co. Rep.
E. REED, P.S.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed Date SEPTEMBER 3, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28
REVISED MAY 14, 1975

REVISED JAN. 198
REVISED OCT. 199