

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN
Branch County
Recorded

For corners in

BRANCH (County)	Located In:	Corner Code #
SHERWOOD TWP.		
1. Public Land Survey	T 5 S R 8 W	K - 05
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10-30-1996 09:23:10

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0093**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD R. REED, P.S. a field survey on SEPTEMBER 03, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SHERWOOD TWP. T5S, R8W

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
SECTION CORNER 11-12-13-14, T5S, R8W, SHERWOOD TWP.

G.L.O. FIELDNOTES, JOHN MULLETT, D.S., 1826: "North between Sec's 13 & 14. 80.00 Set post cor sec's 11, 12, 13 & 14. Beech 16 N25E 6. Beech 8 S36 1/2 W 34."
Old Section Corner File Card (Section 12) = "Iron".
Old Section Corner File Card (Section 14) = "Pipe".
E.R. Reed, County Surveyor, March 1964: Fieldnotes for "BYADAMSITE" subdivision: Pd. 1" iron pipe in N-S fenceline"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 1" iron pipe which references the plat of "BYADAMSITE", about 2 inches below ground surface, and by a north-south fenceline (east one of two fences).
Set a 1/2" x 24" steel rebar rod with Branch County Remonumentation Cap in pipe (top of pipe driven to about 10" deep), and placed concrete around same. Remonument Cap stands about 0.5' above ground.
And is accepted as a careful and faithful perpetuation of the position of the original corner.


ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON OCT. 9, 1996

E.R. Reed Co Rep
E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENT CAP ON 1/2" x 24 REBAR IN I. PIPE (SET IN CONCRETE)
Placed Carsonite Witness Post beside Corner Monument.

- N 80 W 6.61' - Nail, S. side 8" Poplar.
- S 05 W 3.63' - Nail & spotter, W. side 8" Hackberry.
- N 00 W 5.60' - Nail & spotter, W. side 6" Poplar
- N 90 W 1.00' - Center of 3" Hackberry.
- N-S fenceline, 8 ft. West. N-S fenceline, 1ft. East



Signed by *Edward R. Reed* Edward R. Reed, P.S. Date September 03, 1996

Surveyor's Michigan License No. 7437