

SURVEY & REMONUMENTATION

FEB 13 2001

BRANCH COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded

SECTION

For corners in

<u>BRANCH</u>	Located In:	Corner Code #	
(County)			
SHERWOOD TOWNSHIP	T <u>5S</u> R <u>8W</u>	<u>K-11</u>	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

12-15-2000 14:07:44

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0128

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on NOVEMBER 17, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO: JOHN MULLETT, D.S. 1826
OLD SECTION CORNER FILE CARD: "STONE" (FROM E.R. REED, COUNTY SURVEYOR)
SURVEY OF SECTION 36, T5S, R8W, BY C. HAMILTON, COUNTY SURVEYOR, 1881:
FOUND CORNER IN TAMARACK SWAMP.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-2000

E. Reed, P.S.
E. REED, Co. REP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

OLD FENCE ON WEST LINE OF SECTION 36 STOPS SEVERAL HUNDRED FEET SOUTH OF CORNER. PROJECTED THIS FENCE LINE NORTH TO CENTERLINE OF FRANCISCO ROAD ON NORTH LINE OF SECTION 36 AND DUG AND FOUND LARGE TRIANGULAR STONE (18" x 16" ±) WITH MANY SMALLER STONES AROUND IT IN BLACK DIRT 1' ± BELOW GRAVEL SURFACE. MOVED STONE TO WEST AND PLACED 1/2" STEEL ROD AND CAP.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BRANCH COUNTY REMONUMENTATION 1/2" STEEL ROD AND CAP STAMPED NO. 20704 IN MONUMENT BOX 6" BELOW GRAVEL SURFACE.
R.R. TIE FENCE POST, N40°E 55.9 FEET
R.R. TIE FENCE POST, N10°E 89.2 FEET
UTILITY POLE, S05°E 71.25 FEET (NAIL AND SPOTTER)
ON CENTERLINE OF E-W GRAVEL ROAD
N 1/4 CORNER, SECTION 36, EAST 2647.63 FEET.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704

NOTICE
COPY IS FOR BRANCH COUNTY DEPARTMENTAL MAP-
RING PURPOSES ONLY THIS COPY NOT TO BE REPRODUCED AND PUBLIC TO REGISTERED NEEDS FOR COPIES



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995