

SECTION

BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded

For corners in

BRANCH (County)	Located In:	Corner Code #
SHERWOOD TOWNSHIP	T <u>5S</u> R <u>8W</u>	<u>L-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

12-30-1999 11:02:01

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0057

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on NOVEMBER 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY JOHN MULLETT, D.S. 1826
CHAS. HAMILTON, COUNTY SURVEYOR, 1881, ORIGINAL CORNER LOST, SET STAKE AND STONE AT MID POINT OF SECTION LINE.
CHAS. HAMILTON, COUNTY SURVEYOR 1903, FOUND LIGHTENING ROD SET IN STONES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER FALLS IN ROAD CUT. NO OLD WITNESSES REMAINING.
DUG AND FOUND 1/2" IRON 1 FOOT, MORE OR LESS, DEEP.
ACCEPTED FOUND 1/2" IRON AS BEST EVIDENCE OF ORIGINAL CORNER.
REPLACED 1/2" IRON WITH BRANCH COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12/07/99

E. R. Reed, P.S.
E. R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BRANCH COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX
10" WHITE OAK, N03°E 47.10 FEET, SET NAIL AND SPOTTER
7" HICKORY, S20°E 34.13 FEET, SET NAIL AND SPOTTER
18" HICKORY, S60°W 64.27 FEET, SET NAIL AND SPOTTER
7" ELM, N35°W 35.46 FEET, SET NAIL AND SPOTTER
3.5' ± SOUTH OF CENTERLINE OF E&W ROAD
IN LINE WITH TREE LINE TO NORTH.

Signed by _____
Surveyor's Michigan License No. 20704 ROBERT R. CARR

