SURVEY &
REMONUMENTATION

MAR 2 1 1997

COMMISSION

BRANCH COUNTY REMONUMENTATON CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded
12-30-1996 14:12:01
Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00003 Page 0111
Register of Deeds Stamp & File Number

For corners in

BRANCH (County)

	Located In:	Corner Code ##
1. SHERWOOD TWP. Public Land Survey	T 5S R 8W	M-5
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Sec.	S ___ T ___ R ___	

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____



I, EDWARD W. REED , in a field survey on NOVEMBER 4 , 19 96 , *do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned* in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 *above were in* conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: **Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1826: J. MULLETT, DEP. SURVEYOR, CORNER SET
1826: R. CLARK, G.L.O FIELDNOTES FOR "UNION TWP. A-5" SHOWS OFFSET 122 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG LARGE HOLE, UNABLE TO LOCATE ANY EVIDENCE OF CORNER
RESET ON SECTION LINE, G.L.O. DISTANCE OFFSET FROM A-5 UNION
SET 1/2" x 18" IRON, REMONUMENTATION CAP AND SET CAST IRON BOX FLUSH WITH ROAD SURFACE

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Nov. 13, 1996
E.R. Reed, Co. Rep.
E.R.REED

STATE OF MICHIGAN
EDWARD W. REED
LAND SURVEYOR
NO. 33985
LICENSED LAND SURVEYOR

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2 x 18" IRON WITH REMONUMENTATION CAP AND CAST IRON BOX
N80E 19.4' TO FACE OF CONCRETE FENCE POST
N60W 40.72' TO NAIL & WASHER ON SOUTH SIDE OF POWER POLE
10.3' N-S ROAD DUE WEST
122 LINKS NORTH OF A-5 UNION
S10E 82.1' TO CENTER OF 48" MAPLE

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed EDWARD W. REED Date NOVEMBER 4, 1996
Surveyor's Michigan License No. 33985

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1
REVISED MAY 14, 1
REVISED JAN., 1