

SECTION

BRANCH COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded

12-15-2000 14:08:04

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0130

Register of Deeds Stamp & File Number

For corners in

BRANCH	Located In:	Corner Code #
(County)		
SHERWOOD TOWNSHIP	T 5S R 8W	M-11
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on NOVEMBER 17, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: JOHN MULLETT, D.S. 1825
BEECH 8 SOUTH 8, ELM 26 N56W 10.
SURVEY OF SECTION 36, T5S, R8W BY C. HAMILTON, COUNTY SURVEYOR, 1881:
FOUND OLD STAKE HOLE, PLANTED LONG STONE FOR CORNER AND MADE DEPOSIT OF IRON EARTHEN AND SMALL STONES. NO TREES NEAR FOR WITNESSES.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 343 OF 1930 AT A MEETING HELD ON 11-28-2000

E. R. Reed P.S.
E. R. REED, Co. REP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MONUMENTATION BY HAMILTON, 1881 APPEARS TO HAVE BEEN REMOVED BY ROAD CONSTRUCTION AS CORNER FALLS IN DITCH CUT ON NORTH SIDE OF FRANCISCO ROAD. REESTABLISHED CORNER BY PROJECTING NORTH LINE OF SECTION 36 FROM NW CORNER (FOUND LARGE TRIANGULAR STONE) THROUGH N 1/4 CORNER, SECTION 36 (PREVIOUSLY REMONUMENTED IN 1999) TO INTERSECT LINE OF OLD FENCE RUNNING SOUTH ON EAST LINE OF SECTION 36. THIS LOCATION PUTS NORTH 1/4 CORNER ON LINE AND AT MIDPOINT OF NORTH LINE OF SECTION 36 AS PER HAMILTON SURVEY OF 1881; HOWEVER, DISTANCE IS SHORT 7.55 FEET EACH HALF.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BRANCH COUNTY REMONUMENTATION 1/2" STEEL ROD WITH CAP STAMPED NO. 20704 IN MONUMENT BOX 6" BELOW BOTTOM OF DITCH ON NORTH SIDE OF FRANCISCO ROAD.
CENTER 5" STEEL POST, N25°W 7.0 FEET
CENTER 12" DIA. CONCRETE POST, SOUTH 55.5 FEET
UTILITY POLE, SOUTH 78.3 FEET (NAIL AND SPOTTER)
16" MAPLE, S02°W 72.0 FEET (NAIL AND SPOTTER)
36" MAPLE, S33°E 73.5 FEET (NAIL AND SPOTTER)
23.4 FEET MORE OR LESS NORTH OF CENTERLINE OF PAVEMENT.
CORNER TO SECTIONS 30 AND 31, T5S, R7W, SOUTH 46.86 FEET.

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOV 28 2000

