

**SURVEY &  
REMONUMENTATION**

FEB 08 1999

**SECTION**

**BRANCH COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u>	Located in:	Corner Code #
<u>BUTLER TWP</u>		
1. Public Land Survey	<u>T 5 S R 5 W</u>	<u>A-7</u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
3. Miscellaneous	S <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
Property in Sec.	S <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>

STATE OF MICHIGAN  
Branch County  
Recorded

11-04-1998 15:45:41

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on MAY 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHWEST CORNER, SECTION 18  
NORTHWEST CORNER, SECTION 19

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-09-1998  
E.R. Reed, Co. Rep. **E.R. REED**

A. Description of original monument and accessories and/or subsequent restoration:

1825: R. CLARK, JR, D.S. - CORNER SET  
1958: E.R. REED, CO SURVEYOR - CALLS FOR SQUARE HEADED IRON  
1978: E.R. REED, CO SURVEYOR - FOUND SQUARE HEADED IRON USED BEFORE, SET 1/2" IRON PIPE OVER IRON TO RAISE TO ROAD SURFACE, RECORDED IN LCRC # 0217

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE OVER SQUARE HEADED IRON AS DESCRIBED IN LCRC # 0217

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

42" MAPLE (STUMP) S 80 W 57.9 TO CENTER  
WOOD CORNER POST S 06 E 40.6' TO FACE  
SQ. CONC ANCHOR POST NORTH 49.7' TO NEAR FACE  
P. POLE S 03 E 40.8' TO FACE  
GIRARD TWP SIGN POST N 60 W 71.4' TO FACE  
10.7' SOUTH OF CENTERLINE OF GIRARD ROAD

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Edward W. Reed  
EDWARD W. REED

Date 9-9-98

Liber 00003 Page 0207

Surveyor's Michigan License No. 33985